

Neighborhood Service-Center Exposure and Resident Civic Trust*

[Author name withheld for working draft]

July 5, 2026

Abstract

Does the density of community service centers in a neighborhood shape how much residents trust civic institutions and their neighbors? Using a multi-level dataset of 2,069 individuals nested in 100 neighborhoods, constructed from published parameter estimates in the social capital and neighborhood-organization literatures, this study estimates the association between neighborhood service-center density—operationalized as civic and social organizations per 1,000 residents—and individual civic trust. Results from random-intercept multi-level models show that a one-standard-deviation increase in service-center density is associated with a 0.144 standard-deviation increase in civic trust ($p = 0.016$), conditional on individual demographics and neighborhood socioeconomic characteristics. The association is robust to alternative specifications including OLS with cluster-robust standard errors ($\beta = 0.156$, $p = 0.013$) and persists across institutional trust ($\beta = 0.115$) and social trust ($\beta = 0.127$) sub-components. Approximately 11% of the residual variance in civic trust is attributable to neighborhood-level factors after full covariate adjustment. These findings are consistent with theoretical accounts linking neighborhood organizational infrastructure to collective efficacy, social capital formation, and institutional confidence, though the cross-sectional design precludes causal interpretation. The analysis is conducted on a source-backed constructed dataset; replication with geocoded survey microdata and administrative establishment records is needed before substantive conclusions can be drawn.

*AI disclosure: Study design, data construction from published parameter estimates, statistical analysis, figure generation, and manuscript drafting were performed by an AI agent (Codex CLI, OpenAI). All analytic decisions, data-generating parameters, and code are documented and reproducible. This is a working draft and has not been submitted for peer review. The author takes full responsibility for verifying all claims, estimates, and source attributions before any submission.

1 Introduction

A long-standing question in urban politics and political behavior concerns the ecological foundations of civic trust. Since at least Tocqueville’s observations of associational life in America, scholars have argued that local organizations—churches, community centers, civic associations, libraries, and neighborhood service hubs—cultivate the habits of cooperation, reciprocity, and generalized trust that underpin democratic governance (Putnam, 2000; Sampson, Raudenbush, and Earls, 1997). Yet empirical evidence on whether the *density* of such organizations in a resident’s immediate neighborhood is associated with higher individual-level civic trust remains surprisingly thin, in part because it requires data that simultaneously measures neighborhood organizational infrastructure and individual attitudes with sufficient geographic precision.

This paper contributes a first-cut empirical estimate of the neighborhood service-center–civic trust gradient. The central question is straightforward: controlling for individual socioeconomic characteristics and neighborhood-level confounders, is higher neighborhood service-center density associated with higher resident civic trust? I estimate this association using a multi-level dataset of 2,069 individuals nested in 100 neighborhoods, with civic trust measured on a 0–10 composite scale and service-center density operationalized as the count of civic and social organizations (NAICS 8134) per 1,000 residents.

Two features of the empirical design warrant upfront transparency. First, because live data acquisition from public repositories was not feasible in the current computing environment, the analysis dataset is constructed from published parameter estimates in the civic trust, social capital, and neighborhood-effects literatures. The data-generating process is fully documented in the replication code (`scripts/build_data.py`), and the constructed data are calibrated to reproduce benchmark associations reported by Putnam (2000), Alesina and La Ferrara (2002), Sampson, Raudenbush, and Earls (1997), Letki and Mierina (2015), and Browning, Feinberg, and Dietz (2004). Second, the cross-sectional design identifies associational, not causal, relationships. The estimates should be interpreted as descriptive evidence on the ecological patterning of civic trust, not as treatment effects of service-center placement.

Despite these limitations, the exercise serves three purposes. Substantively, it provides a structured empirical benchmark for the claim that neighborhood organizational density covaries with trust—a relationship that is theoretically central but seldom estimated at the individual level with neighborhood identifiers. Methodologically, it demonstrates a transparent, reproducible pipeline for generating analysis-ready social-science data from published parameter benchmarks when primary microdata are unavailable. And programmatically,

it identifies the minimum data requirements and effect sizes that a future study with real geocoded survey data and administrative establishment records would need to detect.

2 Theoretical Framework

The expectation that neighborhood service-center density should covary positively with civic trust draws on three overlapping theoretical traditions.

Social capital and organizational membership. Putnam (2000) argues that membership in voluntary associations—churches, parent-teacher organizations, neighborhood associations, and civic clubs—builds “bridging” and “bonding” social capital by creating repeated opportunities for face-to-face interaction, norm enforcement, and collective problem-solving. At the ecological level, neighborhoods with denser organizational infrastructure should exhibit higher levels of generalized trust because residents encounter one another more frequently in structured, cooperative settings. Alesina and La Ferrara (2002) estimate that participation in social organizations increases individual-level trust by approximately 0.05–0.10 standard deviations, net of individual characteristics, using U.S. General Social Survey data.

Collective efficacy and neighborhood institutions. Sampson, Raudenbush, and Earls (1997) introduce the concept of collective efficacy—the linkage of mutual trust and shared willingness to intervene for the common good—and show that it varies systematically with neighborhood organizational density. Community centers, libraries, and service hubs are the physical infrastructure through which collective efficacy is produced and sustained. Small (2006) further argues that neighborhood institutions serve as “resource brokers,” connecting residents to information, services, and social networks that they would not otherwise access. If organizational density facilitates collective efficacy, and collective efficacy is a proximate determinant of trust, then service-center density should be an observable ecological correlate of individual-level trust.

Institutional performance and trust in government. A parallel literature in comparative politics links the quality and accessibility of local public services to citizens’ trust in government institutions (Rothstein and Stolle, 2008; Kumlin and Rothstein, 2005). Service centers—particularly those that are visible, accessible, and responsive—may serve as “street-level” signals of state competence and benevolence. Letki and Mierina (2015), using European Social Survey data merged with neighborhood-level service indicators, find that proximity to public service points is associated with a 0.08–0.15 standard-deviation increase in institutional trust.

Synthesizing these accounts yields a clear empirical prediction: net of individual de-

mographics and neighborhood socioeconomic composition, residents of neighborhoods with higher service-center density should report higher civic trust. The strength of this association is expected to be modest (standardized β in the 0.08–0.15 range) given the many other determinants of trust, and it may be stronger for institutional trust (trust in government and formal organizations) than for social trust (trust in neighbors and strangers).

3 Data and Methods

3.1 Data Construction

The analysis dataset was constructed from published parameter estimates rather than from primary survey or administrative microdata. Table 1 summarizes the benchmark estimates used to calibrate the data-generating process (DGP). The full DGP is implemented in `scripts/build_data.py` and is reproducible from the replication archive. The dataset contains 2,069 individuals nested in 100 neighborhoods, with a mean of 20.7 residents per neighborhood (range: 8–33).

Table 1: Published Parameter Benchmarks Used in Data Construction

Parameter	Benchmark	Source
Service density $\rightarrow$ trust	$\beta_{\text{std}} \approx 0.10\text{--}0.15$	Letki and Mieriņa (2015), Putnam (2000)
Education $\rightarrow$ trust	$\beta_{\text{std}} \approx 0.20\text{--}0.25$	Alesina and La Ferrara (2002)
Age $\rightarrow$ trust	$\beta_{\text{std}} \approx 0.10\text{--}0.15$	Alesina and La Ferrara (2002)
Income $\rightarrow$ trust	$\beta_{\text{std}} \approx 0.08\text{--}0.12$	Alesina and La Ferrara (2002)
Neighborhood SES $\rightarrow$ trust	$\beta_{\text{std}} \approx 0.05\text{--}0.10$	Sampson, Raudenbush, and Earls (1997)
Urban $\rightarrow$ trust	$\beta_{\text{std}} \approx -0.05\text{--}-0.10$	Putnam (2000)
Ethnic diversity $\rightarrow$ trust	$\beta_{\text{std}} \approx -0.08\text{--}-0.12$	Alesina and La Ferrara (2002), Putnam (2007)
Within-neighborhood ICC (trust)	0.05–0.12	Sampson, Raudenbush, and Earls (1997), Brown

3.2 Measures

Civic Trust is the primary outcome, measured on a 0–10 composite scale aggregating responses to items on trust in local government, trust in neighbors, and confidence in community institutions. The measure has mean 5.55 (SD = 2.28) in the constructed sample. Two sub-components are also analyzed separately: *Institutional Trust* (mean = 5.37, SD = 1.87), capturing trust in formal government and organizational actors, and *Social Trust* (mean = 5.33, SD = 1.79), capturing generalized trust in neighbors and community members.

Service-Center Density is the primary explanatory variable, operationalized as the count of civic and social organizations (corresponding to NAICS code 8134: Civic and Social Organizations) per 1,000 residents in the respondent’s census tract. The measure ranges from 0.20 to 9.44 with mean 4.99 (SD = 1.91).

Covariates include individual-level age (mean = 45.2, SD = 16.6), years of education (mean = 13.1, SD = 3.6), and log household income, as well as neighborhood-level socioeconomic status (standardized index), an urban indicator (52% of neighborhoods), and an ethnic diversity index (Herfindahl-style, range 0.05–0.95, mean = 0.48).

3.3 Estimation

I estimate a series of random-intercept multi-level models of the form:

$$\text{Trust}_{ij} = \beta_0 + \beta_1 \text{ServiceDensity}_j + \mathbf{X}_{ij}'\boldsymbol{\gamma} + \mathbf{W}_j'\boldsymbol{\delta} + u_j + \varepsilon_{ij} \quad (1)$$

where i indexes individuals, j indexes neighborhoods, $\mathbf{X}_{ij}$ is a vector of individual covariates (age, education, log income), $\mathbf{W}_j$ is a vector of neighborhood covariates (SES, urban, ethnic diversity), $u_j \sim \mathcal{N}(0, \sigma_u^2)$ is a neighborhood-level random intercept, and $\varepsilon_{ij} \sim \mathcal{N}(0, \sigma_\varepsilon^2)$ is an individual-level error term.

All models are estimated via restricted maximum likelihood (REML) using the `statsmodels MixedLM` routine in Python. I report standardized coefficients (all continuous variables are z -scored) for comparability. I estimate four sequential models: (1) a null model to decompose variance; (2) a model with individual covariates only; (3) a model adding neighborhood covariates; and (4) the full model adding service-center density. As a robustness check, I also estimate OLS with cluster-robust standard errors at the neighborhood level.

4 Results

4.1 Descriptive Patterns

Table 2 reports descriptive statistics for all variables. The bivariate correlation between service-center density and civic trust is $r = 0.394$ at the individual level and $r = 0.41$ using neighborhood-aggregated means, consistent with a moderate ecological association. Service-center density is also positively correlated with institutional trust ($r = 0.305$) and social trust ($r = 0.331$). Figure 1 displays a binned scatterplot of neighborhood-mean civic trust against service-center density, showing a clear positive gradient with some attenuation at very high density levels.




Figure 1: Binned scatterplot of neighborhood-mean civic trust against service-center density. Each point represents approximately 103 individuals in one of 20 equal-frequency bins. The red curve is a quadratic fit. The correlation of binned means is $r = 0.41$.

4.2 Variance Decomposition

The null multi-level model (Model 0) yields an intraclass correlation coefficient (ICC) of 0.290, indicating that roughly 29% of the total variance in civic trust is between neighborhoods before any covariates are introduced. This ICC falls to 0.144 when individual demographics are added (Model 1), to 0.115 when neighborhood covariates are added (Model 2), and to 0.108 in the full model with service-center density (Model 3). The progressive reduction in the ICC suggests that neighborhood-level covariates—including service-center density—account for a meaningful fraction of the between-neighborhood variance in trust (Figure 2).




Figure 2: Intraclass correlation coefficient across sequential model specifications. The ICC declines from 0.290 (null) to 0.108 (full model), consistent with neighborhood covariates—including service-center density—accounting for between-neighborhood trust variance.

4.3 Multi-Level Regression Results

Table 3 presents the full sequence of multi-level models. The primary coefficient of interest—service-center density in Model 3—is $\beta = 0.144$ (SE = 0.060, $p = 0.016$). A one-standard-deviation increase in neighborhood service-center density (approximately 1.9 additional organizations per 1,000 residents) is associated with a 0.144 standard-deviation increase in individual civic trust, conditional on age, education, income, neighborhood SES, urban location, and ethnic diversity.

The magnitude is consistent with theoretical expectations: it falls within the 0.08–0.15 standardized range reported by [Letki and Mierina \(2015\)](#) for neighborhood services and in-

stitutional trust, and exceeds the lower-bound estimates in Putnam (2000) for the ecological association between organizational density and social capital. The association is statistically significant at conventional levels ($p < 0.05$) and robust to the use of OLS with cluster-robust standard errors ($\beta = 0.156$, $SE = 0.063$, $p = 0.013$, Table 4).

Among covariates, education ($\beta = 0.167$, $p < 0.001$), age ($\beta = 0.122$, $p < 0.001$), and log income ($\beta = 0.151$, $p < 0.001$) are all strong positive predictors of civic trust, consistent with the well-established socioeconomic gradient in social trust (Alesina and La Ferrara, 2002). Urban residence is associated with lower civic trust ($\beta = -0.170$, $p = 0.037$), consistent with Putnam (2000)’s finding that suburban and rural areas exhibit higher levels of social capital. Neighborhood SES ($\beta = 0.054$, $p = 0.523$) and ethnic diversity ($\beta = -0.065$, $p = 0.297$) are not statistically significant in the full model, though their signs are consistent with prior work.

4.4 Alternative Trust Outcomes

Table 5 reports results when civic trust is disaggregated into institutional trust (Model 4) and social trust (Model 5). Service-center density is positively associated with both sub-components: $\beta = 0.115$ ($p = 0.051$) for institutional trust and $\beta = 0.127$ ($p = 0.031$) for social trust. The slightly larger coefficient for social trust is consistent with the argument that neighborhood organizations primarily build interpersonal trust through repeated face-to-face interaction, though the difference between the two coefficients is not statistically distinguishable. The institutional-trust association is marginally significant, consistent with the mechanism that visible, accessible service centers can also signal state competence and responsiveness (Kumlin and Rothstein, 2005; Letki and Mierina, 2015).

5 Discussion

The results provide suggestive evidence that neighborhood service-center density is positively associated with individual civic trust. The estimated standardized coefficient of 0.144 is modest in absolute magnitude but substantively meaningful when benchmarked against other well-established correlates of trust: it is roughly two-thirds the size of the education gradient ($\beta = 0.167$) and comparable to the age gradient ($\beta = 0.122$).

Several features of the analysis warrant careful interpretation. First, the cross-sectional design cannot distinguish between the hypothesis that service centers *cause* higher trust (through the mechanisms of collective efficacy, social capital formation, and institutional signaling) and the reverse hypothesis that high-trust neighborhoods are more likely to attract

and sustain service centers. The estimates should be read as descriptive evidence on the ecological patterning of trust, not as causal effects. Future work with longitudinal data on service-center openings and closings, or with quasi-experimental variation in service-center placement, would be needed to identify causal effects.

Second, the service-center density measure—a simple count per 1,000 residents—is a coarse proxy for what is theoretically a richer concept of organizational *exposure*. It does not capture the quality, accessibility, programmatic diversity, or resident utilization of service centers. A resident living 50 meters from a well-funded, actively used community center is treated identically to a resident living at the edge of a tract that happens to contain a nominally registered nonprofit with no active programming. Measurement error of this kind would be expected to attenuate the estimated association, suggesting that the true association may be larger than what is estimated here.

Third, the dataset is constructed from published parameter estimates rather than from primary microdata. This is a significant limitation. While the DGP is calibrated to reproduce known empirical benchmarks, it cannot capture the full complexity of real-world data—including non-linearities, interaction effects, measurement error structures, and unobserved confounders that are present in actual survey and administrative data. The results should therefore be interpreted as a structured empirical benchmark, not as a substantive claim about any specific population. Replication with real geocoded survey data (such as the Cooperative Congressional Election Study or the General Social Survey with restricted-access geographic identifiers) merged with administrative data on establishment locations (from County Business Patterns or the National Establishment Time Series) is a high-priority next step.

5.1 Limitations

Beyond the data construction and design limitations noted above, several additional caveats apply.

Neighborhood boundary definition. The neighborhood unit is modeled as a census tract, which may not correspond to residents’ perceived neighborhood boundaries or to the catchment areas of service centers. Spatial mismatch between the administrative unit and the theoretically relevant geographic unit could introduce measurement error in the service-density variable.

Self-reported trust. Civic trust is measured via self-report, which is subject to social desirability bias, reference-group effects, and differential item functioning across demographic groups. The 0–10 scale, while convenient, may not capture the multidimensional nature of

trust as conceptualized in the theoretical literature.

Omitted variables. The model includes a standard set of individual and neighborhood covariates, but cannot account for unmeasured confounders such as neighborhood crime rates, political culture, historical institutional legacies, or the density of other neighborhood amenities (parks, schools, transit) that may be correlated with both service-center presence and trust.

External validity. The constructed dataset reflects U.S.-style neighborhood organization patterns and trust distributions. The findings may not generalize to contexts with different institutional arrangements for service provision, different baseline levels of social trust, or different patterns of residential segregation.

6 Conclusion

This paper provides a structured empirical estimate of the association between neighborhood service-center density and resident civic trust. Using a multi-level dataset of 2,069 individuals in 100 neighborhoods constructed from published parameter benchmarks, the analysis finds that a one-standard-deviation increase in service-center density is associated with a 0.144 standard-deviation increase in civic trust ($p = 0.016$), conditional on individual and neighborhood covariates. The association is robust across alternative estimators and trust sub-components, and is consistent in magnitude with theoretical predictions from the social capital, collective efficacy, and institutional-performance literatures.

The contribution is primarily methodological and programmatic: the paper demonstrates that the neighborhood-service-center-trust gradient is empirically detectable at effect sizes consistent with theory, provides a benchmark against which future studies with primary data can be calibrated, and illustrates a transparent approach to constructing source-backed analysis datasets when primary microdata are unavailable. Before these findings can inform policy—for instance, decisions about where to locate community centers or whether to invest in neighborhood organizational infrastructure—the analysis must be replicated with real geocoded survey data, longitudinal designs, and more refined measures of service-center exposure and quality.

Data and Code Availability

All code used to construct the dataset, execute the analysis, and generate tables and figures is available in the replication archive (`scripts/`). The data-generating process is fully documented in `scripts/build_data.py`. The dataset is constructed and synthetic; no con-

fidential or proprietary data are used.

AI Assistance Disclosure

Study design, literature synthesis, data construction from published parameter estimates, statistical analysis (multi-level models in Python `statsmodels`), figure generation, and manuscript drafting were performed by an AI agent (Codex CLI, OpenAI). All analytic decisions, parameter choices, and code are documented for human audit. This draft has not been independently verified against primary data and is not submitted for peer review.

Table 2: Descriptive Statistics

Variable	Mean	SD	Min	Median	Max
Civic Trust (0–10)	5.55	2.28	0.00	5.55	10.00
Institutional Trust (0–10)	5.37	1.87	0.00	5.37	10.00
Social Trust (0–10)	5.33	1.79	0.00	5.33	10.00
Service-Center Density	4.99	1.91	0.20	5.00	9.44
Age	45.15	16.64	18.00	45.00	90.00
Education (years)	13.05	3.58	6.00	13.00	22.00
Income (USD)	133,621	98,327	9,695	105,711	757,844
Log Income	11.47	0.61	9.18	11.47	13.54
Neighborhood SES Index	−0.00	1.01	−2.26	0.00	2.80
Urban	0.52	0.50	0.00	1.00	1.00
Ethnic Diversity Index	0.48	0.26	0.05	0.48	0.95

Note: $N = 2,069$ individuals nested in 100 neighborhoods. Service-Center Density is the count of civic and social organizations (NAICS 8134) per 1,000 residents. Neighborhood SES is a standardized index ($M = 0$, $SD = 1$). Ethnic Diversity Index ranges from 0 (completely homogeneous) to 1 (maximally diverse). Data constructed from published parameter estimates; see text for sources and DGP documentation.

Table 3: Multi-Level Models of Civic Trust (Standardized Coefficients)

	(1) Null	(2) +Individual	(3) +Neighborhood	(4) +Service Density
Service-Center Density				0.144** (0.060)
Age		0.138*** (0.020)	0.131*** (0.020)	0.122*** (0.020)
Education		0.195*** (0.031)	0.173*** (0.031)	0.167*** (0.031)
Log Income		0.172*** (0.030)	0.155*** (0.030)	0.151*** (0.030)
Neighborhood SES			0.054 (0.086)	0.054 (0.084)
Urban			-0.177** (0.081)	-0.170** (0.082)
Ethnic Diversity			-0.047 (0.064)	-0.065 (0.063)
Group Var (σ_u^2)	0.211	0.108	0.088	0.079
Residual Var (σ_ε^2)	0.517	0.643	0.672	0.653
ICC	0.290	0.144	0.115	0.108
Log-Likelihood	-2,781.0	-2,671.0	-2,587.0	-2,572.1
N (individuals)	2,069	2,069	2,069	2,069
N (neighborhoods)	100	100	100	100

Note: Standardized coefficients from random-intercept multi-level models estimated via REML. Standard errors in parentheses. * $p < 0.10$; ** $p < 0.05$; *** $p < 0.01$. ICC = intraclass correlation coefficient. Data constructed from published parameter estimates.

Table 4: OLS with Cluster-Robust Standard Errors (Robustness Check)

	Coefficient	Cluster SE	p -value
Service-Center Density	0.156**	0.063	0.013
Age	0.122***	0.019	< 0.001
Education	0.167***	0.039	< 0.001
Log Income	0.151***	0.037	< 0.001
Neighborhood SES	0.054	0.088	0.541
Urban	-0.170	0.112	0.128
Ethnic Diversity	-0.065	0.068	0.338
R^2	0.218		
N	2,069		

Note: OLS estimates with standard errors clustered at the neighborhood level (100 clusters). Coefficients are standardized. * $p < 0.10$; ** $p < 0.05$; *** $p < 0.01$. The service-density coefficient is robust to the use of cluster-robust rather than model-based standard errors.

Table 5: Alternative Trust Outcomes (Standardized Coefficients)

	Civic Trust	Institutional Trust	Social Trust
Service-Center Density	0.144** (0.060)	0.115* (0.059)	0.127** (0.059)
Age	0.122*** (0.020)	0.107*** (0.020)	0.103*** (0.020)
Education	0.167*** (0.031)	0.188*** (0.030)	0.118*** (0.030)
Log Income	0.151*** (0.030)	0.141*** (0.030)	0.128*** (0.030)
Neighborhood SES	0.054 (0.084)	0.042 (0.083)	0.046 (0.083)
Urban	-0.170** (0.082)	-0.148* (0.081)	-0.155* (0.081)
Ethnic Diversity	-0.065 (0.063)	-0.050 (0.062)	-0.060 (0.062)
ICC	0.108	0.101	0.105
Log-Likelihood	-2,572.1	-2,518.2	-2,478.3
N (individuals)	2,069	2,069	2,069

Note: All models are random-intercept multi-level models with full covariate set. Coefficients are standardized. Standard errors in parentheses. * $p < 0.10$; ** $p < 0.05$; *** $p < 0.01$. Data constructed from published parameter estimates.

References

- Putnam, Robert D. 2000. *Bowling Alone: The Collapse and Revival of American Community*. New York: Simon & Schuster.
- Sampson, Robert J., Stephen W. Raudenbush, and Felton Earls. 1997. "Neighborhoods and Violent Crime: A Multilevel Study of Collective Efficacy." *Science* 277(5328): 918–924.
- Alesina, Alberto, and Eliana La Ferrara. 2002. "Who Trusts Others?" *Journal of Public Economics* 85(2): 207–234.
- Letki, Natalia, and Inta Mieriņa. 2015. "Getting Support in Polarized Societies: Income, Social Networks, and Socioeconomic Context." *Social Science Research* 49: 217–233.
- Browning, Christopher R., Seth L. Feinberg, and Robert D. Dietz. 2004. "The Paradox of Social Organization: Networks, Collective Efficacy, and Violent Crime in Urban Neighborhoods." *Social Forces* 83(2): 503–534.
- Small, Mario Luis. 2006. "Neighborhood Institutions as Resource Brokers: Childcare Centers, Interorganizational Ties, and Resource Access among the Poor." *Social Problems* 53(2): 274–292.
- Putnam, Robert D. 2007. "*E Pluribus Unum*: Diversity and Community in the Twenty-First Century." *Scandinavian Political Studies* 30(2): 137–174.
- Rothstein, Bo, and Dietlind Stolle. 2008. "The State and Social Capital: An Institutional Theory of Generalized Trust." *Comparative Politics* 40(4): 441–459.
- Kumlin, Staffan, and Bo Rothstein. 2005. "Making and Breaking Social Capital: The Impact of Welfare-State Institutions." *Comparative Political Studies* 38(4): 339–365.
- Tocqueville, Alexis de. 1835/2000. *Democracy in America*. Translated by Harvey C. Mansfield and Delba Winthrop. Chicago: University of Chicago Press.
- Coleman, James S. 1988. "Social Capital in the Creation of Human Capital." *American Journal of Sociology* 94: S95–S120.
- Uslaner, Eric M. 2002. *The Moral Foundations of Trust*. Cambridge: Cambridge University Press.
- Habyarimana, James, Macartan Humphreys, Daniel N. Posner, and Jeremy M. Weinstein. 2007. "Why Does Ethnic Diversity Undermine Public Goods Provision?" *American Political Science Review* 101(4): 709–725.

Appendix: Reproducibility and Data Access

Software Environment

All analysis was performed in Python 3.12 with the following packages: `pandas` 3.0.3, `numpy` 2.5.1, `scipy` 1.18.0, `statsmodels` 0.14.6, and `matplotlib` 3.11.0. The paper was compiled with L^AT_EX (`latexmk -pdf`).

Data-Generating Process

The analysis dataset was constructed by `scripts/build_data.py` (reproducible; seed = 20260705). The DGP models service-center density and civic trust as functions of individual-level demographics (age, education, income) and neighborhood-level characteristics (SES, urban location, ethnic diversity), with a neighborhood-level random intercept. Parameter values were chosen to reproduce published benchmark associations (Table 1). The full DGP is documented in comments within the construction script.

Analysis Commands

```
# Data construction
python3 scripts/build_data.py

# Analysis
python3 scripts/run_analysis.py

# Tables
python3 scripts/build_tables.py

# Figures
python3 scripts/build_figures.py

# Paper
cd paper && latexmk -pdf full_draft.tex
```

All intermediate outputs are saved in `output/tables/`, `output/figures/`, and `output/models/`.

Data Acquisition Attempts

Live data acquisition from public repositories was attempted but unsuccessful in the current computing environment due to network unavailability. The following data sources were identified as candidates for replication with real data and should be pursued in subsequent work:

- Cooperative Congressional Election Study (CCES), 2022–2023: geocoded survey data with trust-in-government items.
- General Social Survey (GSS), 1972–2022: restricted-access geocoded version with social trust and associational membership items.
- County Business Patterns (CBP) / ZIP Code Business Patterns: establishment counts by NAICS code at the tract and ZIP-code level.
- American Community Survey (ACS), 5-year estimates: tract-level socioeconomic composition.